

CURB AND SIDEWALK NOTES:

- 1.EXPANSION JOINT MATERIAL TO BE 1/2" THICK PREFORMED BITUMINOUS IMPREGNATED FIBER JOINT FILLER.
- 2.CURBS TO HAVE EXPANSION JOINTS INSTALLED AT 10 FT INTERVALS.
- 3. SIDEWALKS TO HAVE EXPANSION JOINTS INSTALLED AT 20 FT INTERVALS AND TOOL JOINTS AT 4 FT INTERVALS.
- 4.EXPANSION JOINT TO BE INSTALLED BETWEEN CURBS AND CONCRETE SIDEWALKS.

BAY HEAD BOROUGH CURB AND PAVEMENT DETAIL

NOT TO SCALE